



VELUX®

VEL-N-20-00035-00001

Skylight Model FCM (9994)
Tempered over Laminated Heat-Strengthened (i89)
0.02 LoE3, Argon-filled IGU

Puits de lumière modèle FCM (9994),
Trempe sur blanc laminé renforcit à la chaleur
0.02 LoE3, unité d'isolation de verre rempli d'argon

ENERGY PERFORMANCE RATINGS
ÉVALUATION DU RENDEMENT ÉNERGÉTIQUE

U-Factor
Valeur-U

(U.S./I-P) **0.42**
(Metric/SI) **2.38**

Solar Heat Gain Coefficient
Coefficient de gain chaleur solaire

0.27

ADDITIONAL PERFORMANCE RATINGS
ÉVALUATION SUPPLÉMENTAIRE DU RENDEMENT

Visible Transmittance
Transmission Visible

0.62

Air Leakage
Infiltration d' Air

(U.S./I-P) **-** (Metric/SI)

Manufacturer stipulates that these ratings conform to applicable NFRC procedures for determining whole product performance. NFRC ratings are determined for a fixed set of environmental conditions and a specific product size. NFRC does not recommend any product and does not warrant the suitability of any product for any specific use. Consult manufacturer's literature for product performance information.

www.nfrc.org

Seelon le fabricant, ces cotes sont conformes aux procédures applicables du NFRC servant à établir le rendement global du produit. Les cotes NFRC sont établies selon les conditions environnementales et des dimensions de produit spécifiques. NFRC ne recommande aucun produits et ne garantie aucun produits dans leurs applications et recommandations d'installations. Consultez la littérature du fabricant pour de l'information sur le rendement de tout autre produit.

www.nfrc.org


ENERGY STAR® Certified in Highlighted Regions
Certifié ENERGY STAR dans les régions en surbrillance

Canada
energystar.gc.ca

U.S. / É.U.
energystar.gov

DO NOT REMOVE UNTIL FINAL INSPECTION / NE PAS RETIRER AVANT L'INSPECTION FINALE

Meets or Exceeds C.E.C. Air Infiltration Requirements



WINDOW & DOOR
MANUFACTURERS ASSOCIATION

WDMA

Hallmark Certified

www.wdma.com

VELUX Model
FCM 4646 0004
Licensee: 426-H-701

Ratings for above size and smaller
Manufacturer Stipulates Conformance as indicated below

| STANDARD | RATING |
|------------------------------------|--|
| AAMA/WDMA/CSA 101/I.S.2/A440-11 | SKG-PG120 Size Tested: 1305 x 1305 mm (51 x 51 in) DP = 11990 Pa (250 psf) |
| AAMA/WDMA/CSA 101/I.S.2/A440-08 | Class CW-PG90 Size Tested: 1305 x 1305 mm (51 x 51 in) DP = 8390 Pa (175 psf) |
| CSA A440S1-09 | DP: +8390/-4309 Pa (+175/-90 psf) Water Test Pressure = 720 Pa (15 psf) Canadian Air Infiltration/Exfiltration = Fixed Level |

TDi Product Evaluation
SK-03
Florida Prod. Approval
13303

18.4 mm Pane
LA Research Report
25885

**KEEP LABEL FOR
CODE INSPECTION
AND HOME RECORDS**

www.veluxusa.com
www.velux.ca
1-800-88-VELUX

VELUX America Inc.
PO Box 5001
Greenwood, SC 29648

VELUX®