

304742

LABEL IS TO BE HUNG AT FINAL ASSEMBLY. Clamp between Ceiling Ring and Trim Ring.



VELUX®

www.veluxusa.com
www.velux.ca
1-800-88-VELUX

- REMOVE ONLY AFTER FINAL INSPECTION
- RETAIN FOR YOUR RECORDS

Florida Prod. Approval 6393

TDI Product Evaluation SK-12

TDI Product Evaluation SK-15


 WINDOW & DOOR MANUFACTURERS ASSOCIATION
WDMA
 Hallmark Certified
 www.wdma.com

TCR 014
 VELUX® SUN TUNNEL™
 Licensee: 426-H-706

Manufacturer Stipulates Conformance as indicated below

CONFORMS TO

RATING

AAMA/WDMA/CSA 101/I.S.2/A440-11

TDDCC-PG165
 Size Tested: 356 mm
 Positive (Download) DP = 14,364 (300 psf)

AAMA/WDMA/CSA 101/I.S.2/A440-08

CW-PG125 – 356 MM – TDD
 Positive (Download) DP = 9,576 Pa (200 psf)

CSA A440S1-09

DP: +9576 / -5985 Pa (+200 / -125 psf)
 Water Test Pressure = 720 Pa (15 psf)
 Canadian Air Infiltration/Exfiltration = A3

The below only applies to product codes ending with 1000US and 1000USE0

ASTM E-1996-05 /
ASTM E-1886-05

Cycle Pressure +50/-50
 Wind Zone 3 Missile Level C